BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42433

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work:Improvements and Maintenance of parks in BEL 2nd Block in Ward No.10 (Doddabommasandra)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of "VINOD KUMAR K S" ( )	
				In Figures	In Words
1	46.52	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	205.66	Rupees Two Hundred Five and Sixty Six Paise Only
2	44.72	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4775.91	Rupees Four Thousand Seven Hundred Seventy Five and Ninety One Paise Only
3	29.81	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5075.46	Rupees Five Thousand Seventy Five and Forty Six Paise Only
4	298.12	Construction of footpath/separator by providing a 150 mm compacted granular sub-base as per Clause 401 & 25mm thick cement concrete grade M-15, overlaid with precast concrete tiles in cement mortar 1:3 including provision of all drainage arrangements but excluding kerb channel etc complete as per specifications and directions of engineer in charge of the work	Sqm	644.96	Rupees Six Hundred Forty Four and Ninety Six Paise Only
5	533	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	No	381.92	Rupees Three Hundred Eighty One and Ninety Two Paise Only
6	96	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	34.64	Rupees Thirty Four and Sixty Four Paise Only
7	96	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	79.57	Rupees Seventy Nine and Fifty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
10/09